


# Emergency Action Update Ascon Landfill Site

January 3, 2006  
Huntington Beach City Council Study Session



## PRESENTED BY

### **Thomas Cota, Chief**


Southern California Cleanup Operations Branch, Cypress Office  
Department of Toxic Substances Control, State of California  
(Lead Agency Providing Regulatory Oversight)

## IN CONJUNCTION WITH

### **Tamara Zeier**

Project Navigator, Ltd.  
(Project Manager for the Responsible Parties of the Ascon Landfill Site)





CALIFORNIA ENVIRONMENTAL PROTECTION AGENCY  
DEPARTMENT OF TOXIC SUBSTANCES CONTROL

---

---

# **Emergency Action - Update**

## **Ascon Landfill Site**


*Presented By:*

**Thomas Cota, Chief**

*Southern California Clean-Up Operations Branch*  
*January 3, 2006*



# Site Location







## What was the “emergency?”


- There may be potential failure of the berm along Hamilton Avenue in the event of high water conditions (e.g., next rainy season).
- Berm failure could result in a release of hazardous substances potentially causing an endangerment to public health and the environment.
- DTSC issues an Imminent or Substantial Endangerment determination on May 13, 2005
- DTSC approves an Emergency Action Workplan on July 13, 2005



# **Aerial View After Heavy Rains** **January 15, 2005**










# View Looking East on North Berm

## January 2005





# Emergency Response Actions Objectives

---

---

- Stabilize the north berm to prevent potential failure.
- Increase the Factor of Safety to prevent potential release of hazardous substances.
- Mitigate seeps along northern edge of Site.
- Complete emergency response actions prior to 2005/2006 winter heavy rains.





# **DTSC's Public Outreach Activities**

- 
- 
- Brief City of Huntington Beach City Council, June 20, 2005
  - Emergency Response Action Fact Sheet
  - Public notice in local newspapers
  - Public meeting July 6, 2005
  - Notified community prior to beginning fieldwork
  - 24-hour hotline
  - Met with Edison High School and School District staff
  - Held an informational open house






# Emergency Action Update Ascon Landfill Site

January 3, 2006

Huntington Beach City Council Study Session



*PRESENTED BY*

**Tamara Zeier**

Project Navigator, Ltd.  
(Project Manager for the Responsible Parties of the Ascon Landfill Site)



***Project Navigator, Ltd.***

# **Emergency Action Update**

## **Ascon Landfill Site**

***Presented by:***



**Tamara Zeier**

***Project Manager for the Ascon Landfill Site Responsible Parties  
Project Navigator, Ltd.***

# **Emergency Action (EA) and Site Maintenance Work**



# Summary of Emergency Action



## Emergency Action Metrics

- Total truck trips: ~2,600 trucks
- ~40,000 cy of drilling mud removed
- Total of ~48,000 cy (~62,000 tons) material removed
- Daily avg. material shipped offsite: ~975 tons/day
- Daily avg. truck trips: ~40 trucks/day
- Disposal facility: all loads were shipped to Kettleman Hills

# Excavation in Lagoon 4



Continuous application of foam suppressant while excavating drilling muds

## Excavating northern side of Lagoon 4

In addition to water, foam suppressants, and misters used at the Site for odor and emissions control, Soil Seal was applied to excavated areas at the end of the work day.




# Excavation in Lagoon 4




Portoon-mounted excavator used to excavate the drilling mud from the lagoon

Application of foam suppressant while excavating drilling muds

Excavator bucket loading excavated material into onsite Moxy truck to bring to stockpile staging area



Concrete buttress along south side of Lagoon 4 (used to strengthen an internal berm)






# Berm Excavation and Grading



Compacting the berm material  
after excavation




Application of foam suppressant  
while excavating the berm


Excavating and grading the  
north berm slope

# North Berm (along Hamilton Ave.)


## With Erosion Control Blanket, Applied After Hydroseeding



# North Berm Toe Drain



Toe drain sump




Pipe installation inside the toe drain






# Stormwater Controls

## Eastern and Western Sides of Site





Hydroseeded eastern drainage swale



Hydroseeding the western drainage swale

# Stormwater Controls

## South Side of Site




# **Emergency Action**

## **Air Monitoring and Sampling**



# EA Air Monitoring Locations



## LEGEND

- Ascon Landfill Site Boundary
- Pits and Lagoons Boundaries
- Meteorological Monitoring Station  
(to monitor wind conditions)
- Air Monitoring and Sampling  
Location (Approximate) for Real -  
Time and Time-Integrated  
Sampling (monitoring for odors,  
dust, and chemical vapors)

Note: Air sampling was conducted at an elevated location during the berm reconstruction.

# EA Real-Time Air Monitoring

- Included monitoring for Total Volatile Organic Compounds (VOCs) hourly at 7 perimeter locations each work day
- Odor monitoring also conducted
- To date, real-time monitoring conducted for a total of 129 days totaling approximately 9,030 measurements
- 4 of the 9,030 measurements exceeded stop-work criteria
- When stop-work criteria were exceeded:
  - Work was stopped
  - Vapor control measures implemented until readings were below action level
  - SUMMA canister sample analysis expedited
- Chemical-specific analyses indicated no significant off-site exposures were occurring based on regulatory approved comparison criteria

# EA Time-Integrated Air Sampling


- SUMMA canister samples collected at perimeter locations during each work day
- Laboratory analysis for individual VOCs
- To date, air sampling analyzed for a total of 109 days totaling 652 measurements
- No measurements exceeded acute (1 hour to 14 day exposure) or intermediate (15 to 365 day exposure) comparison criteria
- 7 of the 652 measurements exceeded chronic comparison criteria (>365 days to lifetime exposure) for only one chemical, naphthalene
- Exposure above the chronic level would need to occur every day for greater than 1 year before health effects might be observed
- Therefore, the observed exceedances did not result in a significant off-site exposure
- Results analyzed by certified lab & independently reviewed by DTSC



# Air Monitoring Results Summary


- Few times stop-work action was needed
- Odors were observed during excavation activities
- Although odors observed and work was stopped infrequently, chemical-specific analyses indicated that no significant off-site exposures were occurring based on regulatory approved comparison criteria
- DTSC posted results on its website

# Air Sampling



High volume air sampler (PM-10 sampler collecting airborne dust particulates and associated metal concentrations)

High volume air sampler (Puff sampler sampling polycyclic aromatic hydrocarbons)



Summa canister (to measure for volatile organic compounds)

# Real-time Air Monitoring




Air monitoring at perimeter with hand held instrument to give 'real-time' readings

Air monitoring within 3 inches of excavated material with hand held instrument per South Coast Air Quality Management District (SCAQMD) permit






# Odor and Emission Suppressants



Soil Seal was applied on all stockpiles



In order to better control odors & emissions, a foam suppressant was applied at the working face of the excavation in Lagoon 4.




Misters spraying suppressant to help control odors




# Transportation and Disposal

# Landfill Material Removal Process Flow Chart



Truck entering Site




Truck entering staging area




Lining truck bed with plastic



Trucks being loaded



Truck being weighed (also cleaned and tarped at this station)



Driver receiving manifest for truck load




Truck leaving Site



Truck on Beach Blvd. by 405 on-ramp going toward disposal site



Drilling mud being excavated




Mud being loaded onto Moxy truck



Mud being mixed with drier soil




# Transportation and Disposal Requirements



Sampling the material to profile and properly dispose of at appropriate disposal facility

Air monitoring within 3 inches of excavated material with hand held instrument while sample was collected per South Coast Air Quality Management District permit




Truck driver receiving manifest to haul material to appropriate disposal facility


# Key Findings/Lessons Learned

- Method of excavating drilling mud from lagoons using pontoon-mounted excavator worked well
- Berm reshaping proved our assumptions were accurate regarding weakness of the berm materials
- Over 1 million truck miles traveled without incident
- Odors were difficult to manage and despite our continual efforts, there were still some nuisance odors present, but no unacceptable health risk to the community
- All activities completed safely and majority of work completed on schedule


# Looking Forward



# Site Cleanup Process







# **Ascon Key Activities**

---

---

- Groundwater Remedial Investigation
- Second Feasibility Study
  - Soil/Waste and Groundwater
- Remedial Action Plan
- Environmental Impact Report
- Implementation of Remedy